Wesdome Gold Mines Ltd
TSX: WDO
OTCQX: WDOFF
www.wesdome.com

WESDOME EXPANDS HIGH-GRADE ZONES AT EAGLE RIVER, HIGHLIGHTING GROWTH POTENTIAL NEAR EXISTING INFRASTRUCTURE

Wesdome Gold Mines News Release, November 2, 2026 – Drill Hole Table

Note about length of zones: The length of holes was use for all Zones and mineralized corridors in this release, since true width needs to be determined with further modelling in all sectors. The Zones extension and possible thickness are being tested with further exploratory drilling and using a wide corridor, not to limit the potential of discovery of more potential intercepts.

Table: Eagle River Drill Assay Results (Previously Unreleased)

Figures in table may not add due to rounding

Eagle River

Hole No.	From (m)	To (m)	Core Length (m)	Grade (g/t Au)	Grade (capped) (g/t Au)	Zone
26-1201-36	446.77	449.03	2.18	96.19	26.24	500
including	448.41	449.03	0.62	345.00	90.00	500
	446.77	447.60	0.83	3.84	3.84	500
	447.60	448.00	0.40	0.08	0.08	500
	448.00	448.41	0.41	0.68	0.68	500
	448.41	449.03	0.62	345.00	90.00	500
26-1201-36	149.19	151.20	2.01	8.89	8.89	700
including	149.70	150.13	0.43	41.00	41.00	700
	149.19	149.71	0.52	1.03	1.03	700
	149.71	150.13	0.42	41	41	700
	150.13	150.63	0.50	0.02	0.02	700
	150.63	151.2	0.57	0.098	0.098	700
26-1201-36	88.70	91.00	2.30	13.28	13.28	800 area
including	89.40	90.00	0.60	41.00	41.00	800 area
	88.70	89.40	0.70	8.36	8.36	800 area
	89.40	90.00	0.60	41.00	41.00	800 area
	90.00	90.60	0.60	0.06	0.06	800 area
	90.60	91.00	0.40	0.07	0.07	800 area
26-1201-34	415.10	415.73	0.63	23.00	23.00	500
	415.10	415.73	0.63	23.00	23.00	500
26-1201-26	201.00	203.00	2.00	25.61	25.61	700
including	201.83	202.45	0.62	70.83	70.83	700
	201.00	201.83	0.83	0.77	0.77	700
	201.83	202.45	0.62	70.83	70.83	700
	202.45	203.00	0.55	12.13	12.13	700

26-350-08	237.42	239.51	2.09	28.95	28.95	700 area
including	237.93	238.34	0.41	51.50	51.50	700 area
including	238.34	239.00	0.66	38.00	38.00	700 area
	237.42	237.93	0.51	8.67	8.67	700 area
	237.93	238.34	0.41	51.50	51.50	700 area
	238.34	239.00	0.66	38.00	38.00	700 area
	239.00	239.51	0.51	19.37	19.37	700 area
25-805-47	186.14	188.71	2.57	12.46	12.46	6 Central area
including	187.36	187.96	0.60	28.70	28.70	6 Central area
	186.14	186.76	0.62	4.14	4.14	6 Central area
	186.76	187.36	0.60	5.98	5.98	6 Central area
	187.36	187.96	0.60	28.70	28.70	6 Central area
	187.96	188.29	0.33	3.93	3.93	6 Central area
	188.29	188.71	0.42	17.50	17.50	6 Central area
25-805-47	215.62	217.37	1.75	14.08	14.08	6 Central
including	216.03	216.39	0.36	66.60	66.60	6 Central
	215.62	216.03	0.41	0.05	0.05	6 Central
	216.03	216.39	0.36	66.60	66.60	6 Central
	216.39	216.84	0.45	1.28	1.28	6 Central
	216.84	217.37	0.53	0.12	0.12	6 Central
26-805-62	4.00	6.00	2.00	30.25	30.25	6 Central/800 corridor
including	4.00	4.50	0.50	56.09	56.09	6 Central/800 corridor
including	4.50	4.98	0.48	31.72	31.72	6 Central/800 corridor
including	5.70	6.00	0.30	43.07	43.07	6 Central/800 corridor
	4.00	4.50	0.50	56.09	56.09	6 Central/800 corridor
	4.50	4.98	0.48	31.72	31.72	6 Central/800 corridor
	4.98	5.36	0.38	5.51	5.51	6 Central/800 corridor
	5.36	5.70	0.34	6.49	6.49	6 Central/800 corridor
	5.70	6.00	0.30	43.07	43.07	6 Central/800 corridor
26-805-61	0.50	2.59	2.09	11.88	11.88	6 Central/800 corridor
including	1.05	1.40	0.35	68.00	68.00	6 Central/800 corridor
	0.50	1.05	0.55	0.04	0.04	6 Central/800 corridor
	1.05	1.40	0.35	68.00	68.00	6 Central/800 corridor
	1.40	1.74	0.34	2.02	2.02	6 Central/800 corridor
	1.74	2.59	0.85	0.37	0.37	6 Central/800 corridor
26-470-14	123.6	126.75	3.15	21.80	21.80	700
including	124.00	125.00	1.00	67.33	67.33	700
	123.60	124.00	0.40	0.70	0.70	700
	124.00	125.00	1.00	67.33	67.33	700

	125.00	126.00	1.00	0.10	0.10	700
	126.00	126.75	0.75	1.30	1.30	700
26-470-18	102.28	104.00	1.72	22.38	22.38	700
including	102.58	102.88	0.30	39.50	39.50	700
including	103.18	103.50	0.32	70.50	70.50	700
	102.28	102.58	0.30	5.60	5.60	700
	102.58	102.88	0.30	39.50	39.50	700
	102.88	103.18	0.30	3.37	3.37	700
	103.18	103.50	0.32	70.50	70.50	700
	103.50	104.00	0.50	2.77	2.77	700
26-470-19	95.90	101.60	5.70	20.22	16.97	700
including	95.90	96.20	0.30	40.73	40.73	700
including	99.10	100.70	1.60	52.89	41.32	700
	95.90	96.20	0.30	40.73	40.73	700
	96.20	96.53	0.33	0.40	0.40	700
	96.53	97.03	0.50	0.37	0.37	700
	97.03	97.70	0.67	0.43	0.43	700
	97.70	98.10	0.40	5.97	5.97	700
	98.10	98.40	0.30	9.43	9.43	700
	98.40	98.80	0.40	10.57	10.57	700
	98.80	99.10	0.30	6.43	6.43	700
	99.10	99.45	0.35	33.70	33.70	700
	99.45	99.80	0.35	14.87	14.87	700
	99.80	100.10	0.30	20.20	20.20	700
	100.10	100.40	0.30	151.70	90.00	700
	100.40	100.70	0.30	53.53	53.53	700
	100.70	101.00	0.30	2.37	2.37	700
	101.00	101.30	0.30	0.00	0.00	700
	101.30	101.60	0.30	19.03	19.03	700
26-470-22	93.90	97.00	3.10	21.46	21.46	700
including	94.50	95.00	0.50	31.10	31.10	700
including	95.00	95.50	0.50	65.70	65.70	700
	93.90	94.50	0.60	11.70	11.70	700
	94.50	95.00	0.50	31.10	31.10	700
	95.00	95.50	0.50	65.70	65.70	700
	95.50	96.00	0.50	5.54	5.54	700
	96.00	97.00	1.00	8.34	8.34	700
26-470-06	117.00	118.00	1.00	39.80	39.80	700
including	117.00	118.00	1.00	39.80	39.80	700

	117.00	118.00	1.00	39.80	39.80	700
26-470-20	90.35	92.09	1.74	16.55	16.55	700
including	91.70	92.09	0.39	43.97	43.97	700
	90.35	90.85	0.50	12.13	12.13	700
	90.85	91.17	0.32	14.83	14.83	700
	91.17	91.7	0.53	1.57	1.57	700
	91.7	92.09	0.39	43.97	43.97	700
26-925-03	262.70	270.65	7.95	8.26	8.26	800
including	263.03	263.40	0.37	41.41	41.41	800
including	269.00	269.47	0.47	83.53	83.53	800
	262.70	263.03	0.33	1.55	1.55	800
	263.03	263.40	0.37	41.41	41.41	800
	263.40	263.75	0.35	0.4	0.4	800
	263.75	264.10	0.35	3.48	3.48	800
	264.10	264.45	0.35	2.89	2.89	800
	264.45	264.80	0.35	0.66	0.66	800
	264.80	265.15	0.35	2.26	2.26	800
	265.15	265.45	0.30	2.91	2.91	800
	265.45	265.85	0.40	2.44	2.44	800
	265.85	266.20	0.35	0.3	0.3	800
	266.20	266.55	0.35	0.002	0.002	800
	266.55	267.00	0.45	0.002	0.002	800
	267.00	267.55	0.55	0.002	0.002	800
	267.55	268.50	0.95	0.5	0.5	800
	268.50	269.00	0.50	1.13	1.13	800
	269.00	269.47	0.47	83.53	83.53	800
	269.47	269.77	0.30	2.83	2.83	800
	269.77	270.15	0.38	1.47	1.47	800
	270.15	270.65	0.50	5.5	5.5	800
26-925-10	298.80	309.40	10.60	8.25	5.85	800
including	299.25	299.80	0.55	18.20	18.20	800
including	303.95	304.43	0.48	143.00	90.00	800
	298.80	299.25	0.45	1.02	1.02	800
	299.25	299.80	0.55	18.20	18.20	800
	299.80	300.15	0.35	0.04	0.04	800
	300.15	300.53	0.38	3.41	3.41	800
	300.53	301.08	0.55	0.24	0.24	800
	301.08	301.70	0.62	0.44	0.44	800
	301.70	302.06	0.36	0.08	0.08	800

	302.06	302.50	0.44	0.72	0.72	800
	302.50	302.85	0.35	0.25	0.25	800
	302.85	303.50	0.65	0.25	0.25	800
	303.50	303.95	0.45	0.70	0.70	800
	303.95	304.43	0.48	143.00	90.00	800
	304.43	304.93	0.50	0.47	0.47	800
	304.93	305.50	0.57	0.34	0.34	800
	305.50	306.15	0.65	0.25	0.25	800
	306.15	306.55	0.40	2.89	2.89	800
	306.55	307.05	0.50	0.32	0.32	800
	308.08	308.50	0.42	1.23	1.23	800
	308.50	309.00	0.50	0.10	0.10	800
	309.00	309.40	0.40	5.57	5.57	800
26-925-04	222.64	223.06	0.42	25.43	25.43	800
	222.64	223.06	0.42	25.43	25.43	800
	222.64	223.06	0.42	25.43	25.43	800
26-925-09	341.78	342.25	0.47	10.50	10.50	800
	341.78	342.25	0.47	10.50	10.50	800
	341.78	342.25	0.47	10.50	10.50	800
26-925-11	348.70	349.00	0.30	32.51	32.51	800
	348.70	349.00	0.30	32.51	32.51	800
	348.70	349.00	0.30	32.51	32.51	800
26-805-50	437.50	439.00	1.50	8.96	8.96	800
including	438.50	439.00	0.50	15.20	15.20	800
	437.50	438.00	0.50	8.33	8.33	800
	438.00	438.50	0.50	3.35	3.35	800
	438.50	439.00	0.50	15.20	15.20	800
26-805-49	465.00	466.00	1.00	12.23	12.23	800
	465.00	466.00	1.00	12.23	12.23	800
	465.00	466.00	1.00	12.23	12.23	800
26-805-48	311.50	312.00	0.50	37.87	37.87	800 area
	311.50	312.00	0.50	37.87	37.87	800 area
	311.50	312.00	0.50	37.87	37.87	800 area
ERS-2026-001-W1	918.00	919.00	2.00	9.70	9.70	800
	918.00	919.00	1.00	19.00	19.00	800
	917	917.5	0.50	0.336	0.336	800
	917.5	918	0.50	0.686	0.686	800
	918	918.5	0.50	36.1	36.1	800
	918.5	919	0.50	1.89	1.89	800

TECHNICAL DISCLOSURE

At the beginning of the 2026 campaign, conversion drilling was completed in BQ size, and the core was sampled in full. Underground exploration holes drilled in NQ size began to follow the same procedure as surface drilling: the core was cut in half with a diamond saw, with one half of the core sample sent for assay and the other half retained for reference.

The sampling of, and assay data from, Eagle River mine drill core is monitored through the implementation of a quality assurance - quality control (QA/QC) program designed to follow industry best practice. Underground drill samples are transported in sealed bags to the Eagle River laboratory in Wawa, Ontario (which is operated by Wesdome, is not independent, and is not accredited), along with an electronic Chain of Custody that itemizes each sample. Samples are analyzed for gold using standard fire assay technique with gravimetric finish. Wesdome inserts blanks and certified reference standards into the sample sequence for quality control at the core shack, and the Wesdome laboratory also inserts their own standards and blanks for each certificate. The QA/QC procedure is described in more detail in the Technical Report for the Eagle River Gold Mining Complex, Ontario, Canada filed under the Company's profile on SEDAR+ on April 22, 2022. In 2024, core sample length was changed from 0.3 m to 0.5 m, while respecting lithological contacts. Pulps are sent to SGS (an ISO/IEC 17025:2017 accredited and independent laboratory), as an external laboratory check of Au assay, run in duplicate, with a sample frequency of 30 to 40 samples selected each month.

Due to the increased volume of assays, the service of AGAT Laboratories in Thunder Bay was used as a second Laboratory. Samples were transported in sealed bags by laboratory registered courier trucks and transported to AGAT Laboratories in Thunder Bay, Ontario (an ISO/IEC 17025:2017 accredited and independent laboratory, accredited lab No. 665) for preparation and analysis. Pulps are analyzed by fire assay and AAS finish (AGAT method 202-051). Samples that graded more than 10 g/t Au were subsequently tested by gravimetric (202-064) and metallic screen (202-121) assays. Halved drill core is kept stored at the Eagle River Complex in core racks for long-term storage. Pulps are returned to Wesdome and are stored in a sea-container at the operations office in the Mishi camp. QA/QC is achieved with a 3-sample package (a blank, a pulp duplicate and a commercial gold standard) that are inserted into the sample stream at an interval of 20 samples. Consequently, 15 QA/QC samples are inserted for each 100 samples. Additionally, blanks were inserted after visible gold is observed to prevent contamination between samples.

QUALIFIED PERSONS

The technical content of this release has been compiled, reviewed, and approved by the following employees of Wesdome: Breanne Beh, P.Geo., (PGO #2648) Director Surface and Greenfields Exploration; and Serge Gonthier, P.Geo., (PGO #1849) Principal Geologist, Resources and Geology. Each is a “Qualified Person" as defined in National Instrument 43-101 - Standards of Disclosure for Mineral Projects.